

KARABÜK GROUP 2 (WRS-Kr6) RURAL ROAD BRIDGE CONSTRUCTION



Western Blacksea Region

Employer	: RURAL SERVICES 13 th DISTRICT DIRECTORATE KARABÜK PROVINCE DIRECTORATE
Contract date	: 17.05.2000
Work completion date	: 25.04.2001
Project cost	: 249 379 155 367,00 TL (2000 unit prices) [484 821,82 US\$]

Bridges were fabricated as concrete foundation, concrete abutment over bored piles with prestressed girders.

Karabük - Safranbolu - Bostanbükü - Adalar bridge is $2 \times 20.30 = 40.60$ m span, 9.70 m wide.

Karabük - Safranbolu - Bostanbükü - Karşiyaka bridge is $3 \times 17.50 = 52.50$ m span, 9.70 m wide.

