



OSTİM NATURAL GAS AND COMBINED CYCLE POWER PLANT (41 MW) AND NATURAL GAS LINE CONSTRUCTION



Central Anatolia Region
Ankara - Ostim





Employer : AYEN OSTİM ENERJİ ÜRETİM A.Ş.
Contract date : 28.03.2003
Work completion date : 11.06.2004
Project cost : 5 802 594,48 US \$

The combined cycle natural gas power plant has 41 MW installed power and constructed in the Ankara Ostim OIZ in order to meet the power demands of the district and to trade electricity in free market.

Within the facility there is gas turbine (31.077 MW) steam turbine (9.89 MW), waste heat boiler, water treatment plant, water cooling system and closed switch system.

Within this project scope, 24 km natural gas pipeline, 24 000 nm³/h capacity RMS-A 75/50 barg pressure reducing station, 12 000 nm³/h capacity RMS-B 50/31 barg pressure reducing station were constructed.



AYDINER